

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

**Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92**

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Maintenance of BBMP Drilled Borewells in ward no. 10, Doddabommasandra Vidyaranyapura sub division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	30	Lifting of Submersible pump set as per Specification and direction (P. 56 / I. 10.3.21) PRED SR (2012-13)	Each	850	
2	30	Transportation of pumping machineries (P. 56 / I. 10.3.19) PRED SR (2012-13)	Each	900	
3	30	Labour charges (over hauling) P. No. 56 / I No.10.3.22 PRED SR (2012-13)	Job	550	
4	15	A) Repairs to Motor: Rewinding of submersible pump sets with copper insulation wire of suitable gauge as per ISI specification with guarantee of 6 months. PRED SR (2012-13) P No. 54 / I. No. 10.1) (Above 10 HP upto 20 HP add Rs.150/- for every HP) A) 10 HP Motor upto 5 HP 2500.00 for 10 HP (120 x 10) 1200.00 Total 3700.00	No.	3700	
5	15	B) 12.5 HP Motor upto 5 HP 2500.00 for 12.5 HP (150 x 15) 2250.00 Total 4750.00	No.	4750	
6	30	B) Replacement of Motor Parts: Starter (with one year Guarantee) P No. 55 / I No. 10.3.3 PRED SR (2012-13)	No.	5050	
7	30	Rotor (with one year Guarantee) P No. 55 / I No. 10.3.6) PRED SR (2012-13)	No.	4700	
8	30	Upper Flange P. No. 56 / I No. 10.3.7 PRED SR (2012-13)	No.	350	
9	30	Lower Housing P. No. 56 / I No. 10.3.10 PRED SR (2012-13)	No.	650	
10	30	Carbon Housing P. No. 56 / I No.10.3.12 PRED SR (2012-13)	No.	475	
11	30	Thrust bearing block assembly complete with Segment bearing pad.P. No. 55 / I No.10.3.13 PRED SR (2012-13)	No.	1150	
12	30	C) Replacement of pump parts: The following main components of submersible pump sets requiring replacement. Oil Seal P. No. 54 / I No.10.2.3 PRED SR (2012-13)	No.	125	
13	30	Oil Seal Steel Bush P. No. 54 / I No. 10.2.4 PRED SR (2012-13)	No.	150	
14	450	Guide vane P. No. 54 / I No. 10.2.5 PRED SR (2012-13)	No.	175	
15	450	Impeller Shell moulded with aluminium Bronze) P. No. 54 / I No. 10.2.6 PRED SR (2012-13)	No.	425	
16	30	Discharge outlet (D.O) Bearing D.O Steel Bush P. No. 55 / I No. 10.2.7 PRED SR (2012-13)	No.	445	
17	30	Steel Bush P. No.55 / I No. 10.2.9 PRED SR (2012-13)	No.	150	
18	30	Pump shaft made out of stainless steel Centreless ground with key way (upto 8 stages) P. No. 55 / I No. 10.2.11 PRED SR (2012-13)	No.	950	

19	30	Non – return valve (NRV) assembly complete with rubber 'O' Ring P. No. 55 / I No. 10.2.14 PRED SR (2012-13)	No.	1350	
20	30	Cable Guard P. No. 55 / I No. 10.2.15 PRED SR (2012-13)	No.	150	
21	30	Brass Filter P. No. 55 / I No. 10.2.17 PRED SR (2012-13)	No.	250	
22	30	Re-erection charges of pumping machineries including overhauling and pointing P. No. 56 / I No. 10.3.20 PRED SR (2012-13)	Each	950	
23	37.13	D) General Items Earthwork excavation for pipeline trenches including deporiting or bank up to a lead of 50 mtrs including shiriry and statting danger lighting and using site rails and boming poles at every 100 mtrs wherever necessary as directed in th following strstructure manhole. Page No. 01/ Item No.1.2.2 / PRED SR 2012-13 Hard Soil	cum	188	
24	110	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowering into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the exexcavation Etc., Page No.15 item No.3.4.2 b PRED SR 2012-13.	rmtr	157	
25	37	Refilling the basement and pipeline treanches with secleted available earthe for trench excavation including authority condition in layers from thedi including dispensary of the sunplus earth with a heavy 200 mtrs Page No. 3 / Item No. 1.6 / PRED SR 2012-13	cum	61	

ಕರಡು ಟೆಂಡರ್ ಪಡ್ಕೊಲ್ನ್ಮು
ಶಿಡ್ಕುಪಡಿಗಲ ಸಂಖ್ಯೆ.....(117)
ಶಿಡ್ಕುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿರೆ

ಅಧೀಕ್ಷಕ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬಿಬಿಎಂಪಿ, ಬೆಂಗಳೂರು-92



Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

9/11/14